

REQUEST for TENDER PS-2023-01

***Nakina WPCP and Longlac WPCP – Wastewater
Dechlorination Project***

ADDENDUM #4

ISSUED BY

The Corporation of the Municipality of Greenstone

P.O. Box 70, 1800 Main Street
GERALDTON, ON P0T 1M0
Tel: (807) 854-1100
Fax: (807) 854-1947

This addendum forms and becomes part of **RFT PS-2023-01**.

ADDENDUM #4

REQUEST FOR TENDER
NAKINA WPCP AND LONGLAC WPCP – WASTEWATER DECHLORINATION PROJECT
MUNICIPALITY OF GREENSTONE

PAGE 1 OF 1

FEBRUARY 7, 2023

QUESTIONS AND ANSWERS AS POSED:

Question 1:

The note 13 “power distribution” point A. on drawing E002 for Longlac states new lighting panel LP1 but the panel for Longlac on E001 is PB-A. LP1 is on Nakina with a 15KVA transformer built into it. Need to know if they want that same panel from Nakina drawings on Longlac or just a straight panel for Longlac. Also, they show an integral TVSS on Note 13 D i. on this drawing but not shown in the panel schedule for this panel.

Answer 1:

The specification/drawing E002 incorrectly identifies the panel as LP1. It should refer to PB-A instead. The panel is not integrated with a 15kVA transformer. It should be a 125A, 3-phase, 4-wire, 120/208VAC panel with a minimum of 30 circuits. The TVSS has not be included in the schedule due to lack of space (at 30 circuits – with some spares). If the installation area allows for a larger panel (ex. 42 circuit), include a TVSS as mentioned in Note 13 D i.